

## PROJECT DESCRIPTIONS

The following is a brief description of Price City's annual Class "C" Road Improvements project for 2004. Dates for the construction of each project have been given but may not reflect the exact date in which work will be performed in a certain area. Residents and businesses that will be effected by the work will first be given a general notice by Price City and then a notice will be given by the Contractor 24 hours prior to work in each area. Any questions, comments or concerns about the projects should be directed to the Price City Engineer, Jerry L. Wright Jr., who can be reached at (435) 637-5010. Thank you.

### Bid Schedule A: Road Reconstruction (Nielson Construction)

The work for Bid Schedule A: Road Reconstruction was awarded to Nielson Construction. Construction on the streets listed below is scheduled between July 5 and August 18, 2004. Price City will give general notification by flyer to all residents and businesses effected by the construction. Nielson Construction is required to give notification to all residents and businesses 24 hours prior to beginning any work. The work covered under this schedule involves excavation of existing pavement, grading, placement and compaction of necessary subgrade and road base gravel, and placing a three inch (3") bituminous asphalt surface course including tack oil along all edges. This also includes adjusting all manhole and valve lids to grade and traffic control.

<b>Areas Scheduled for Road Reconstruction</b>	
Castle Ave. (Homestead Blvd. to Castle Heights Dr.)	18850 ft <sup>2</sup>
Castle Heights Dr. (Castle Ave. to 800 N.)	21067 ft <sup>2</sup>
300 E. (200 S. to 300 S.)	15708 ft <sup>2</sup>
<b>TOTAL</b>	<b>55625 ft<sup>2</sup></b>

### Bid Schedule B: Crack Sealing (Kilgore Paving)

The work for Bid Schedule B: Crack Sealing was awarded to Kilgore Paving. Construction on the streets listed below is scheduled between September 13 and October 12, 2004. Price City will give general notification by flyer to all residents and businesses effected by the construction. Kilgore Paving is required to give notification to all residents and businesses 24 hours prior to beginning any work. The work covered under this schedule involves the preparation of existing random asphalt pavement cracks and the application of the bituminous crack sealant. This item shall also include the use of a heat lance to warm and dry the cracks if necessary and traffic control.

<b>Areas Scheduled for Crack Sealing</b>			
Smith Dr. (900 N. to Covecrest Dr.)	46300 ft <sup>2</sup>	200 E. (100 N. to 400 N.)	100362 ft <sup>2</sup>
Covecrest Dr. (Smith Dr. to 300 E.)	36696 ft <sup>2</sup>	800 E. (700 N. to 800 N.)	26822 ft <sup>2</sup>
100 E. (900 N. to Covecrest Dr.)	27879 ft <sup>2</sup>	400 N. (Veterans Lane to 700 E.)	29331 ft <sup>2</sup>
Wadleigh Lane (900 N. to Smith Dr.)	22239 ft <sup>2</sup>	400 E. (100 N. to 400 N.)	111767 ft <sup>2</sup>
200 E. (Covecrest Dr. to New	13200 ft <sup>2</sup>	Carbon Ave. (100 N. to 400 N.)	78698 ft <sup>2</sup>
200 E. (200 S. to 300 S.)	25376 ft <sup>2</sup>	300 S. (200 E. to 300 E.)	17424 ft <sup>2</sup>
200 E. (300 S. to 400 S.)	12862 ft <sup>2</sup>	<b>TOTAL (Both Columns)</b>	<b>548986 ft<sup>2</sup></b>

*Additional streets may be added to the list if all of the delivered material has not been used.*

**Bid Schedule C: Slurry Sealing (Morgan Pavement)**

The work for Bid Schedule C: Slurry Sealing was awarded to Morgan Pavement. Construction on the streets listed below is scheduled between July 5 and August 3, 2004. Price City will give general notification by flyer to all residents and businesses effected by the construction. Morgan Pavement is required to give notification to all residents and businesses 24 hours prior to beginning any work. The work covered under this schedule involves preparation of existing asphalt pavement surfaces by brooming and the application of the emulsified asphalt slurry. This shall include protecting manhole and valve lids from the slurry seal, and traffic control. This shall include cleaning sidewalks and gutters after the slurry seal work is complete.

<b>Areas Scheduled for Type 2 Slurry Seal</b>			
600 E. (Main St. to 400 N.)	103266 ft <sup>2</sup>	Parkway (Cedar Hills Dr..to E. End)	18163 ft <sup>2</sup>
600 E. (200 S. to 500 S.)	56047 ft <sup>2</sup>	Cedar Lane (Parkway to Sagewood)	21622 ft <sup>2</sup>
300 E. (100 S. to 200 S.)	29568 ft <sup>2</sup>	500 N. (100 E. to 300 E.)	70313 ft <sup>2</sup>
300 S. (300 E. to 700 E.)	106482 ft <sup>2</sup>	Park Dr. (500 N. to 550 N.)	20592 ft <sup>2</sup>
200 S. (Carbon Ave. to 700 E.)	94649 ft <sup>2</sup>	400 N. (Carbon Ave. to 100 E.)	39552 ft <sup>2</sup>
500 E. (100 N. to 400 S.)	148020 ft <sup>2</sup>	Veterans Lane (600 N. to 700 N.)	29505 ft <sup>2</sup>
400 S. (400 E. to 700 E.)	63429 ft <sup>2</sup>	300 S. (Carbon Ave. to 100 E.)	25621 ft <sup>2</sup>
500 S. (500 E. to 700 E.)	41606 ft <sup>2</sup>	<b>TOTAL (Both Columns)</b>	<b>904036 ft<sup>2</sup></b>
Cottonwood (Sagewood to S. End)	31601 ft <sup>2</sup>		

<b>Areas Scheduled for Type 3 Slurry Seal</b>			
Railroad Ave. (100 W. to W. End)	48840 ft <sup>2</sup>	100 S. (100 W. to Carbon Ave.)	14003 ft <sup>2</sup>
300 W. (Railroad Ave. to 200 S.)	27540 ft <sup>2</sup>	Crestview Dr.	63862 ft <sup>2</sup>
Park Ave. (200 E. to 300 E.)	7466 ft <sup>2</sup>	200 E. (Hillcrest Dr. to Covecrest Dr.)	16764 ft <sup>2</sup>
600 N. (Park Dr. to 300 E.)	56179 ft <sup>2</sup>	500 E. (400 N. to N. End)	10260 ft <sup>2</sup>
200 W. (400 S. to 500 S.)	12313 ft <sup>2</sup>	<b>TOTAL (Both Columns)</b>	<b>257227 ft<sup>2</sup></b>

**D. Bid Schedule D: Pavement Overlays (Nielson Construction)**

The work for Bid Schedule D: Pavement Overlays was awarded to Nielson Construction. Construction on the streets listed below is scheduled between July 12 and September 1, 2004. Price City will give general notification by flyer to all residents and businesses effected by the construction. Nielson Construction is required to give notification to all residents and businesses 24 hours prior to beginning any work. The work covered under this schedule involves the preparation of existing asphalt pavement by rotomilling, brooming and cleaning the surfaces as specified. The application of the 1 ½" bituminous asphalt surface course overlay shall follow the rotomilling work and shall include tack oil over the entire surface and along all edges. This item shall include adjusting manhole and valve lids to the appropriate grade and traffic control.

<b>Areas Scheduled for Pavement Overlays</b>	
<b>400 North (Carbon Avenue to City Limits)</b>	<b>73762 ft<sup>2</sup></b>

**E. Bid Schedule E: Traffic Paint Striping (Peck Striping)**

The work for Bid Schedule E: Traffic Paint Striping was awarded to Peck Striping. Painting on the majority of Price City streets is scheduled between October 11 and October 30, 2004. The work covered under this schedule will be completed on existing road pavement using acceptable water based paints. The location of the paint striping will be furnished just prior to the beginning of the work. Mostly existing striping will be re-painted with a limited amount of new striping. This shall also include traffic control.